

Publication dated 16th December 1930.

1459

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 2nd January 1931, for constructing a Girder Bridge across Dandavathy River. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. In cases contractors quoting tenders as so much percentage below the estimate rates, the percentages should be based on the rates for different items of works which the contractor wishes to claim during execution.

5. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a Girder Bridge across Dandavathy River" in default of which tenders will be rejected.

6. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

7. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

8. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

9. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Abstract estimate of quantities for constructing a Girder Bridge across Dandavathy River:—

No.	Items of work	Per	Quantity	Estimate rates
				Rs. a. p.
1	Clearing site, cutting bank and removing, blasting cutting bank on both sides.	Lump sum		150-0-0
2	Excavating foundation earth work ...	C.yd.	540	0 6 0
3	Stone jelly concrete in surki mortar ...	C.ft.	3,561	0 6 0
4	Vajradundi or trap stone in mortar for foundation	"	6,543	
5	Do for superstructure sides dressed ...	"	12,551	
6	Laterite stone in clay parapet wall ...	"	1,500	0 6 0
7	Burnt stone slabs 6" thick ...	S.ft.	324	1 2 0
8	Pointing with cement mortar ...	Sqr.	44'08	5 0 0
9	Rolled steel beams 20" x 7½" at 89 lbs. with painting (only fixing charges to be quoted).	Cwt.	324½	15 0 0
10	Teakwood wrought and put up including tarring (fixing charges to be quoted).	C.ft.	317'62	7 0 0
11	Teakwood planking (fixing charges to be quoted) ...	S.ft.	433'50	7 0 0
12	Wooden railing including painting (fixing charges to be quoted).	Sqr.	204'00	3 0 0
13	Rough stone work ...	C.yd.	109	3 8 0
14	Draft clearing on both the banks up and down stream side.	Lump sum		1,500 0 0
15	Unwatering foundation ...	Lump sum		1,000 0 0
16	Earthwork to bank including deviation to road ...	Lump sum		2,000 0 0
17	Metalling over bridge ...	Lump sum		1,000 0 0
18	Diverting halla ...	Lump sum		400 0 0

* A rate of Re. 0-8-0 per C.ft. of laterite stone in mortar is sanctioned. Rate to be quoted for trap stone in mortar.

N.B.—Payments for lump sum provision will be as per details of work done during execution and limited to the tendered lumpsum amounts.

K. VENKATARAMAIA,
Executive Engineer.